

Child Nutrition Services
College Station Independent School District
Success... each life... each day... each hour

MEMORANDUM

To: Mark Pantel
Director of Purchasing

From: Diane Dahm DD
Director of Child Nutrition Services

Date: May 6, 2014

Re: Remodel of Serving Lines

Child Nutrition received four quotes for new serving line counters and equipment for four serving lines at AMCHS.

Pasco Brokerage Inc.	\$292,725.00
Kommercial Kitchens	\$299,974.00
Texas Metal Equipment Company	\$309,498.00
Kirby Restaurant Equipment Co.	\$313,755.00

I recommend utilizing Pasco Brokerage using TASB Buy Board Contract #429-13 for this project.

DIANE DAHM
Director of Child Nutrition

1812 Welsh Street, Suite 140
College Station, Texas 77840
(979) 764-5450 FAX: (979) 764-5585

EDDIE COULSON, Ed.D.
Superintendent of Schools



Quote

05/12/2014

To:
 College Station ISD
 Diane Dahm
 1812 Welsh
 College Station, TX 77840
 9797645450 (Contact)
 9797645585 (Fax)

Project:
 TX College Station ISD - A&M
 Consolidated High School, April
 2014

From:
 Pasco Brokerage Inc
 Amy Leasure
 6465 Chase Oaks Blvd
 Plano, TX 75023-4621
 (972) 596-3350
 (972) 596-2817 (Fax)
 aleasure@pascoinc.net



Pricing per the TASB BuyBoard Contract #429-13.
 Pricing includes standard dock delivery to your location, with line item for installation as noted on this proposal.
 This is a fast track summer installation project.
 Pricing includes removal of existing equipment, to location within College Station ISD, as directed by College Station ISD.

Item	Qty	Description	Sell	Sell Total
175	1 ea	REFRIGERATED SANDWICH UNIT Delfield Model No. 4448N-18M Packed: 1 ea Mega Top Refrigerator, two-section, 48" W, 16.0 cubic feet, (2) doors, (2) 1/1 GN shelves, stainless steel top with polyethylene cutting board & (18) 1/6 size plastic pans, ABS interior sides, stainless steel front & sides, 5" casters, front-breathing rear-mounted refrigeration system, 1/5 hp, cUL, UL, NSF	\$3,020.00	\$3,020.00
	1 ea	115v/60/1-ph, 7.2 amps, NEMA 5-15P, standard		
	1 ea	(3) Year parts & labor warranty standard		
	1 ea	Self-Contained refrigeration, std		
	1 ea	(5) Year compressor warranty standard		
	1 ea	Flat lift-off lid in lieu of standard		
	2 ea	0420104 Door/Drawer lock, original order only, not field installable, per section (not available on glass doors)	\$95.00	\$190.00
	1 ea	Custom INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points.	\$330.00	\$330.00

This does not include any facility or utility modifications/upgrades.

This is for work to be performed during normal business hours, M-F,
 8am-5pm.

******NOTE: DELFIELD MODEL SPECIFIED HAS (18) 1/6 SIZE PANS,
 HOWEVER WRITTEN SPEC CALLS FOR (6) PANS. VERIFY REQUIREMENTS
 BEFORE ORDERING.******

Item	Qty	Description	Sell	Sell Total
			ITEM TOTAL:	\$3,540.00
177	1 ea	REACH-IN REFRIGERATOR, 1 SECTION	\$6,090.00	\$6,090.00
		 Traulsen Model No. AHT132WUT-HHS Packed: 1 ea Spec-Line Refrigerator, Reach-in, one-section, self-contained refrigeration, stainless steel exterior, aluminum interior, standard depth, half-height door or doors with Santoprene® EZ-Clean Gaskets, INTELA-TRAUL™ microprocessor controls, ENERGY STAR®		
	1 ea	1.15v/60/1ph, 7.0 amps, with cord & NEMA 5-15P, standard		
	1 ea	3 year service/labor, 5 year compressor warranty, standard		
	2 ea	Door field rehinging option, per door	\$140.00	\$280.00
	13 ea	Universal tray slide - per pair	\$55.00	\$715.00
	3 ea	Credit for standard plated shelf, deduct	\$-50.00	\$-150.00
	1 ea	Relocate electrical outlet box to bottom	\$315.00	\$315.00
	1 ea	Custom INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points.	\$350.00	\$350.00
This does not include any facility or utility modifications/upgrades.				
This is for work to be performed during normal business hours, M-F, 8am-5pm.				
			ITEM TOTAL:	\$7,600.00
190	1 ea	REACH-IN HEATED CABINET, 1 SECTION	\$5,085.00	\$5,085.00
		 Traulsen Model No. AHF132W-HHS Packed: 1 ea Spec-Line Heated Cabinet, Reach-In, one-section, stainless steel exterior, aluminum interior, standard depth cabinet, half-height door or doors with Santoprene® EZ-Clean Gaskets, INTELA-TRAUL™ microprocessor controls, ENERGY STAR®		
	1 ea	*SPECIAL* 208/60/1ph	\$405.00	\$405.00
	1 ea	3 year service/labor warranty, standard		
	2 ea	Door field rehinging option, per door	\$140.00	\$280.00
	13 ea	Universal tray slide - per pair	\$55.00	\$715.00
	3 ea	Credit for standard plated shelf, deduct	\$-50.00	\$-150.00
	1 ea	Relocate electrical outlet box to bottom	\$315.00	\$315.00
	1 ea	Custom INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points.	\$350.00	\$350.00
This does not include any facility or utility modifications/upgrades.				
This is for work to be performed during normal business hours, M-F, 8am-5pm.				
			ITEM TOTAL:	\$7,000.00
201	1 ea	SERVING COUNTER	\$40,480.00	\$40,480.00
		CounterCraft Model No. Custom Packed: 1 ea		ISD

Item	Qty	Description	Sell	Sell Total
		CounterCraft Custom Serving Counter CounterCraft Model No. SCSL-258 - Open base construction. - 14 gauge S/S top, 2" turn down at front and back with 4" high splash at walls. - Countertop to match height of existing counter. Coordinate installation with existing conditions. - Provide raised insulated platform in the front area of all hot food wells. - Countertop at all hot food wells to be recessed 1" to accommodate 18" X 26" sheet pans. - Three (3) Wells model no. SS-206ETD built-in hot food wells with thermostat and manifold drain line into a common drain. Food wells to be insulated and located within a 1" recess. Run drain line to existing floor sink. - One (1) Keas model no. RSM-HDL hot food breath protector with mirror finish posts. Full service front glass with self service tempered glass display shelf. - One (1) Randell drop in frost top located per drawings. Provide on/off switch in control panel. - One (1) Keas model no. RSM-DL breath protectors with mirror finished posts and two tier glass display shelf and display lights at frost top. Self serve. - One (1) Hatco model GRSSB-6018 built in heated pizza stone. - One (1) Keas model no. RSM-HDL hot food breath protector with mirror finish posts. Self service tempered glass. No second shelf. - Proved waterproof grommets in counter top for each piece of equipment mounted on counter top. - S/S legs at workside of counter. - Modify counter to accommodate Refrigerated Air Screen. - Utilize existing outlets. Field verify all requirements prior to installation. Coordinate NEMA configurations - Coordinate installation of counter with existing half wall. Installation of new counter to be congruent with existing counter installation. - If existing water is available, provide spray hose with all required accessories for water at hot food wells. NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
1 ea		Install Delivery and Installation CounterCraft Model No. D/I ***NOTICE:*** CounterCraft pricing INCLUDES delivery and installation. CounterCraft will deliver the quoted counter(s), uncrate, bring inside building, set in place, complete all field welds and joints, complete all final assembly, level, and start up. This includes all CounterCraft site visits prior to and during fabrication including field dimensions. Final utility (plumbing / electrical) connections not by CounterCraft.		

Item	Qty	Description	Sell	Sell Total
		Removal, disposal, or modification of existing equipment is not included.		
		NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
1 ea		Custom Removal Removal of the existing serving line, deliver to CSISD choice of location within 10 miles.	\$1,850.00	\$1,850.00
		No construction, plumbing, electrical, tile, or concrete work included in this proposal.		
			ITEM TOTAL:	\$42,330.00
206	3 ea	REFRIGERATED AIR SCREEN, 36" Custom Model No. CF-S-3SC Packed: 1 ea Manufacturer: Barker, Change to Hillphoenix CF-S-3SC Self-Contained, Self-Service, Open Front Deli Merchandiser Item #206 ELT-7 (conforms to NSF and UL standards) Dwg # 25194-G Item # 206 ** Profile/Length Attribute ** 36" case length WITH ends - 34" case length without ends 87" O.A. case height 32-1/2" O.A. case depth Slides into counter by others Base deck designed to accommodate (2) milk crates ** Raised front dieboard to 29-3/8" AFF to accept milk crates ** (VERIFY Height) Bullet leg base (6") ** Exterior ** Exterior: Stainless Steel Cornice: to match Exterior Outside back: to match Front Exterior Trim & Base Trim : Brushed Stainless Steel Removable Toekicks on Front and Both Sides (No Rear Toekick) Provide Inverted Silver Locking Roll Shutter Provide Stainless Steel drop in collar to be shipped loose and field installed by others ** End Panel Detail ** Square Glass ends Left and Right - Exterior to match Front - Interior to be Mirror Polished Stainless Steel ** Interior ** Interior: Brushed Stainless Steel Interior trim: burshed Stainless Steel (1) row 14" and (2) rows 16" Lighted Adjustable Glass Shelving ** Rear Doors ** Full-length Reflective Swing, Self-closing Rear Load Doors w/ Locks Hinged left or right (Must Specify)	\$11,735.00	\$35,205.00

Item	Qty	Description	Sell	Sell Total
		Triple Pane w/ Heated Door Frames **Note: Roll Shutter and Rear Load Door Locks will not match, 2 keys required ** ** Electrical & Lighting ** 120-1-60 Ceiling Light Under-shelf lights - T8 741 lighting No nose Light, due to milk crates Energy effecient fans with fan covers Provide 6' UL cord and plug (NEMA L5-20 P) - Electrical to exit out bottom of case Main Power and Light Switch located in Lower Base behind Swing Door w/latch ** Refrigeration & Mechanical ** This is a Self-contained Refrigerated Case Copeland Compressor 1/2 HP Automatic Defrost Internally Equalized Expansion Valve Access: Top Mount Airflow: top to top Floor Drain Required - No electric condensate dissipator pan - Drain to exit out bottom of case Solar digital thermometer 5 year Compressor Warranty		
3 ea		INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points. This does not include any facility or utility modifications/upgrades. This is for work to be performed during normal business hours, M-F, 8am-5pm.	\$740.00	\$2,220.00
			ITEM TOTAL:	\$37,425.00
207	1 ea	REFRIGERATED AIR SCREEN, 48" Custom Model No. CF-5-4SC Packed: 1 ea Manufacturer: Barker, Change to Hillophoenix CF-5-4SC Self-Contained, Self-Service, Open Front Deli Merchandiser Dwg # 25193-G Item # 207 ELT-7 (conforms to NSF and UL standards) ** Profile & Dimensions ** 48"W (overall width including ends) *Custom Dimension* --46"W (overall width not including ends) 32-1/2"D 87"H 6"H Bulfet legs * Milk Crate Option * ** Exterior **	\$17,300.00	\$17,300.00

Item	Qty	Description	Sell	Sell Total
		Case Top: to match exterior Exterior: Stainless Steel --Note: If custom color is selected up-charges may apply Outside Back: To Match Exterior Exterior Trim: Stainless Steel Base Trim: To Match Exterior / removable Swing, Reflective Rear Load Doors with Locks Lockable Roll Shutter in front / Silver Provide Flange to facilitate rear mounting at serving counter top (Please confirm height above floor) --Flange to be located on front and both ends ** End Panels ** Glass End, Left --Exterior Painted to Match Front Panel Glass End, Right --Exterior Painted to Match Front Panel ** Interior ** Interior: Stainless Steel Interior Trim: To Match interior (1) row of 14" and (2) rows of 16" Adjustable, Lighted Glass Shelving Base Deck to accommodate (3) milk crates ** Electrical & Lighting ** 120-1-60 Provide 6'UL Cord & Plug Top Light / T8 741 lamp color NO Nose Light due to milk crates Undershelf Lighting / T8 741 lamp color ** Refrigeration ** Self-Contained Refrigeration High Ambient Copeland Compressor - Top Mount No Dissipater Pan - Floor Drain Available Install Thermostat Automatic Defrost Internally Equalized Expansion Valve Condenser Air Flow: Front to Back --NOTE: Ensure adequate ventilation in counter to accommodate air flow Solar Digital Thermometer 5 Year Extended Compressor Warranty (3/4 HP)		
1 ea		INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points. This does not include any facility or utility modifications/upgrades. This is for work to be performed during normal business hours, M-F, 8am-5pm.	\$740.00	\$740.00
			ITEM TOTAL:	\$18,040.00
213	2 ea	MOBILE ICE CREAM DISPENSER	\$5,205.00	\$10,410.00

Item	Qty	Description	Sell	Sell Total
		Mod-U-Serve Model No. DI-IC-2020-MOD Packed: 1 ea Mod U Serve Mobile Ice Cream Dispenser Mobile Ice Cream Serving Counter-SHALLOW WELL, TWO BASKET, mobile modular, removable hinged stainless steel lid, stainless steel sides, top & interior, 5" swivel casters (2 locking) *** MODIFIED TO SMALLEST FOOTPRINT ***		
2 ea		Custom INSTALL Pasco/Statewide Services Installation includes inside delivery, uncrate, set in place, and hook up to proper utilities per the manufacturers' specifications within 4ft of connection points.	\$285.00	\$570.00
		This does not include any facility or utility modifications/upgrades. This is for work to be performed during normal business hours, M-F, 8am-5pm.		
			ITEM TOTAL:	\$10,980.00

214	3 ea	CUSTOM CounterCraft Model No. Custom Packed: 1 ea Owner Provided, Not in Contract		
-----	------	--	--	--

217	1 ea	SERVING COUNTER CounterCraft Model No. Custom Packed: 1 ea CounterCraft Custom Serving Counter Serving Counter CounterCraft Model No. SCCL-372 - Open base construction. 14 gauge S/S top, 2" turn down at front and back with 4" high splash at wall. - Countertop to match height of existing counter. Coordinate installation with existing conditions. - Provide raised insulated platform in the front area of all hot food wells. - Countertop at all hot food wells to be recessed 1" to accommodate 18" X 26" sheet pans. - Three (3) Wells model no. SS-206ETD built-in hot food wells with thermostat and manifold drain line into a common drain. Food wells to be insulated and located within a 1" recess. Drain wells to newly trenched floor sink. - Three (3) Hatco Hot/Cold built-in food wells with thermostat and manifold drain line into a common drain. Food wells to be insulated and located within a 1" recess. Drain to newly trenched floor sink. - Two (2) Keas model no. RSM-HDL hot food breath protector with mirror finish posts. Full service front glass. Single Shelf. - One (1) T & S Model No. B101 - Prerinse spray with 6'-0" S/S hose and B-KG flange installed at hose penetration. One (1) T & S Model No. 512 - Blending valve mounted on recessed panel. One (1) lot vacuum breaker and back flow preventor at each location. Water to be ran from existing water connection at wall. See drawings for clarification. - One (1) Hatco drop in frost top located per drawings. Provide on/off	\$59,900.00	\$59,900.00
-----	------	--	-------------	-------------

Item	Qty	Description	Sell	Sell Total
		switch in control panel. - One (1) Keas model no. RSM-DL breath protector with mirror finished posts and two tier glass display shelf and display lights at frost top. Self serve. - Proved waterproof grommets in counter top for each piece of equipment mounted on counter top. - S/S legs. - Modify counter to accommodate Refrigerated Air Screen and Reach In Heated Cabinet. Equipment by KEC. - Utilize existing outlets. Field verify all requirements prior to installation. Coordinate NEMA configurations. - Coordinate installation of counter with existing half wall. Installation of new counter to be congruent with existing counter installation. - Provide 4" body section in between existing stub wall with S/S finish.		
		NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
1 ea		Install Delivery and Installation CounterCraft Model No. D/I		
		NOTICE: CounterCraft pricing INCLUDES delivery and installation. CounterCraft will deliver the quoted counter(s), uncrate, bring inside building, set in place, complete all field welds and joints, complete all final assembly, level, and start up. This includes all CounterCraft site visits prior to and during fabrication including field dimensions. Final utility (plumbing / electrical) connections not by CounterCraft. Removal, disposal, or modification of existing equipment is not included.		
		NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
1 ea		Custom Removal Removal of the existing serving line, deliver to CSISD choice of location within 10 miles.	\$2,285.00	\$2,285.00
		No construction, plumbing, electrical, tile, or concrete work included in this proposal.		
			ITEM TOTAL:	\$62,185.00
218	1 ea	SERVING COUNTER	\$51,050.00	\$51,050.00
		CounterCraft Model No. Custom Packed: 1 ea CounterCraft Custom Serving Counter Serving Counter CounterCraft Model No. SCCL-372		
		- Open base construction, 14 gauge S/S top, 2" turn down at front and back with 4" high splash at wall. - Countertop to match height of existing counter. Coordinate installation with existing conditions. - Provide raised insulated platform in the front area of all hot food		

Item	Qty	Description	Sell	Sell Total
		<p>wells.</p> <ul style="list-style-type: none"> - Countertop at all hot food wells to be recessed 1" to accommodate 18" X 26" sheet pans. - Three (3) Hatco built-in hot food wells with thermostat and manifold drain line into a common drain. Food wells to be insulated and located within a 1" recess. Drain to newly trenched floor sink. - One (1) Keas model no. RSM-HDL hot food breath protector with mirror finish posts. Full service front glass. Single Shelf. - One (1) T & S Model No. B101 - Prerinse spray with 6'-0" S/S hose and B-KG flange installed at hose penetration. One (1) T & S Model No. 512 - Blending valve mounted on recessed panel. One (1) lot vacuum breaker and back flow preventor at each location. Water to be ran from existing water connection at hand lav. See drawings for clarification. - One (1) Hatco drop in frost top located per drawings. Provide on/off switch in control panel. - One (1) Keas model no. RSM-DL breath protectors with mirror finished posts and two tier glass display shelf and display lights at frost top. Self serve. - Proved waterproof grommets in counter top for each piece of equipment mounted on counter top. - S/S Legs - Modify counter to accommodate Refrigerated Air Screen, Reach In Refrigerator and Refrigerated Prep Table. Equipment by KEC. - One (1) modified hot food breath protector with mirror finish with 1" round post. Post to be vertical front post only with slight angle towards rear of counter. Full-service height temper glass to be fixed mounted to angle section of post. No heat lamp or display light. This breath protector to be located at the Refrigerated Prep Table. - Utilize existing outlets. Field verify all requirements prior to installation. Coordinate NEMA configurations. - Coordinate installation of counter with existing half wall. Installation of new counter to be congruent with existing counter installation. - Provide 4" body section in between existing stub wall with S/S finish. <p>NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.</p>		
	1 ea	<p>Install Delivery and Installation CounterCraft Model No. D/i</p> <p>***NOTICE:*** CounterCraft pricing INCLUDES delivery and installation. CounterCraft will deliver the quoted counter(s), uncrate, bring inside building, set in place, complete all field welds and joints, complete all final assembly, level, and start up. This includes all CounterCraft site visits prior to and during fabrication including field dimensions. Final utility (plumbing / electrical) connections not by CounterCraft. Removal, disposal, or modification of existing equipment is not included.</p> <p>NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.</p>		

Item	Qty	Description	Sell	Sell Total
	1 ea	Custom Removal Removal of the existing serving line, deliver to CSISD choice of location within 10 miles.	\$2,285.00	\$2,285.00
		No construction, plumbing, electrical, tile, or concrete work included in this proposal.		
			ITEM TOTAL:	\$53,335.00
219	1 ea	SERVING COUNTER CounterCraft Model No. Custom Packed: 1 ea CounterCraft Custom Serving Counter CounterCraft Model No. SCSL-252	\$15,450.00	\$15,450.00
		<ul style="list-style-type: none"> - Open base construction. 14 gauge S/S top, 2" turn down at front and back with 4" high splash at wall. - Countertop to match height of existing counter. Coordinate installation with existing conditions. - Proved waterproof grommets in counter top for each piece of equipment mounted on counter top. - S/S legs. - Modify counter to accommodate Refrigerated Air Screen. - Utilize existing outlets. Field verify all requirements prior to installation. Coordinate NEMA configurations. - Coordinate installation of counter with existing half wall. Installation of new counter to be congruent with existing counter installation. 		
		NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
	1 ea	Install Delivery and Installation CounterCraft Model No. D/I		
		NOTICE: CounterCraft pricing INCLUDES delivery and installation. CounterCraft will deliver the quoted counter(s), uncrate, bring inside building, set in place, complete all field welds and joints, complete all final assembly, level, and start up. This includes all CounterCraft site visits prior to and during fabrication including field dimensions. Final utility (plumbing / electrical) connections not by CounterCraft. Removal, disposal, or modification of existing equipment is not included.		
		NOTE: REMOVAL AND DISPOSAL OF EXISTING COUNTER IS NOT INCLUDED.		
	1 ea	Custom Removal Removal of the existing serving line, deliver to CSISD choice of location within 10 miles.	\$1,850.00	\$1,850.00
		No construction, plumbing, electrical, tile, or concrete work included in this proposal.		
			ITEM TOTAL:	\$17,300.00
801	2 ea	SECURITY GATE Cookson Door Model No. Vista Air Packed: 1 ea	\$14,995.00	\$29,990.00

Item	Qty	Description	Sell	Sell Total
		<p>Cookson Security Gate</p> <p>01. Furnished materials shall include all curtains, stiles, tracks and floor sockets.</p> <p>02. Aluminum is to be 6063 aluminum alloy with T-5 temper.</p> <p>03. Constructed of 6" wide x 0.072" thick full height aluminum panels. Panels are to be framed by full height butt hinges on 7" centers. Panels are to be perforated by 0.25" by 1.25" oblong slots that are in evenly spaced columns and staggered rows.</p> <p>System shall incorporate 4" high truss-like plates at the top and bottom of the closure.</p> <p>04. Finish shall be 0.0004" clear anodizing.</p> <p>05. Members are to be vertical stiles fabricated from rectangular tubing 1.3" x 2.4".</p> <p>Members using floor bolts include dust free, stainless top floor sockets.</p> <p>06. Provide Bi-part assembly. One lock member will retain a hookbolt deadlock activated by keyed cylinders. A second intermediate locking member with a steel floor bolt shall include a full height channel to accept the hookbolt deadlock.</p> <p>a. Lead and trailing end members are to be cylinder controlled lock stiles with selfadjusting, cold rolled steel floor bolts and top bolts through the top of the track into the support.</p> <p>b. Intermediate locking members with cold rolled steel floor bolts are supplied for (up to) every 10'-0" of curtain.</p> <p>07. Overhead track is to be 1.3" wide x 1.8" high and is to accept 1-1/8" diameter roller trolleys. Rollers are to bear on 0.27" thick aluminum surface within the track.</p> <p>Provide track curve radii as needed for grille as shown on drawings.</p> <p>08. Contractor shall make structural or other preparation of the opening to receive track and grille, provide finish or trim to the opening, construct finish or trim to the opening and construct storage pockets as necessary. Site preparations are to be detailed by approved shop drawings.</p> <p>09. Examine all conditions under which grilles are to be installed.</p> <p>10. Verify track layout and grille dimensions, especially the finished floor to the underside of the support dimensions, by actual measurements.</p> <p>11. Install in accordance with the manufacturer's shop drawings and instructions.</p> <p>12. Adjust hardware to function smoothly, and lubricate as recommended by manufacturer.</p>		

Item	Qty	Description	Sell	Sell Total
		13. Clean surfaces and refinish abraded or damaged surfaces to match factory finish.		
		This Includes factory installation by Cookson/Johnson Equipment.		
999	1 ea	BONDS Custom Model No. Custom Packed: ea Payment & Performance Bonds	\$3,000.00	\$3,000.00
			Total	\$292,725.00

Prices Good Until: 05/31/2014

Acceptance: _____ Date: _____

Printed Name: _____

Project Grand Total: \$292,725.00

KOMMERCIAL KITCHENS

FOOD SERVICE EQUIPMENT & SUPPLY

Quote

04/16/2014



www.KommericalKitchens.com
800-962-1555


1900 Freeway Blvd. Rose City, TX 77062 13544 East Freeway Houston, TX 77015
Ph: (409) 769-1199 Fax: (409) 769-8800 Ph: (832) 767-2891 Fax: (832) 767-5588

To:
College Station ISD
Diane Dahm
1812 Welsh
College Station, TX 77840
9797645450 (Contact)
9797645585 (Fax)
ddahm@csisd.org

Project:
College Station ISD
A&M Consolidated High School

From:
Kommercial Kitchens
Shannon Woodard
1100 Freeway Blvd
Rose City, TX 77662-9419
4097691199
(409)769-1199 (Contact)
4097698800 (Fax)
Shannon@kommercialkitchens.com

Item	Qty	Description
175	1 ea	REFRIGERATED SANDWICH UNIT  Delfield Model No. 4448N-18M Packed: 1 ea Mega Top Refrigerator, two-section, 48" W, 16.0 cubic feet, (2) doors, (2) 1/1 GN shelves, stainless steel top with polyethylene cutting board & (18) 1/6 size plastic pans, ABS interior sides, stainless steel front & sides, 5" casters, front-breathing rear-mounted refrigeration system, 1/5 hp, cUL, UL, NSF 1 ea 115v/60/1-ph, 7.2 amps, NEMA 5-15P, standard 1 ea (3) Year parts & labor warranty standard 1 ea Self-Contained refrigeration, std 1 ea (5) Year compressor warranty standard 2 ea 0420104 Door/Drawer lock, original order only, not field installable, per section (not available on glass doors)
177	1 ea	REACH-IN REFRIGERATOR, 1 SECTION  Traulsen Model No. AHT132WUT-HHS Packed: 1 ea Spec-Line Refrigerator, Reach-in, one-section, self-contained refrigeration, stainless steel exterior, aluminum interior, standard depth, half-height door or doors with Santoprene® EZ-Clean Gaskets, INTELA-TRAUL™ microprocessor controls, ENERGY STAR® 1 ea 115v/60/1ph, 7.0 amps, with cord & NEMA 5-15P, standard 1 ea 3 year service/labor, 5 year compressor warranty, standard 2 ea Door field rehinging option, per door 13 ea Universal tray slide - per pair 3 ea Credit for standard plated shelf, deduct 1 ea Relocate electrical outlet box to bottom
190	1 ea	REACH-IN HEATED CABINET, 1 SECTION

Item	Qty	Description
		Traulsen Model No. AHF132W-HHS Packed: 1 ea Spec-Line Heated Cabinet, Reach-in, one-section, stainless steel exterior, aluminum interior, standard depth cabinet, half-height door or doors with Santoprene® EZ-Clean Gaskets, INTELA-TRAUL™ microprocessor controls, ENERGY STAR®
	1 ea	208/115v/60/1ph, 7.8 amps, standard
	1 ea	3 year service/labor warranty, standard
	2 ea	Door field rehinging option, per door
	13 ea	Universal tray slide - per pair
	3 ea	Credit for standard plated shelf, deduct
	1 ea	Relocate electrical outlet box to bottom
201	1 ea	SERVING COUNTER Custom Model No. SCSL-258 Packed: ea CounterCraft custom serving counter
206	3 ea	MERCHANDISER Barker Co. Model No. CF-5-3SC Packed: ea Refrigerated air screen, 36"
207	1 ea	MERCHANDISER Barker Co. Model No. CF-S-45C Packed: ea Refrigerated air screen, 48"
213	2 ea	MOBILE ICE CREAM SERVING COUNTER Mod-U-Serve Model No. MCT-DI-IC-2020-MOD Packed: ea Mobile Ice Cream Serving Counter - Shallow Well
214		CASH REGISTER By Owner
217	1 ea	SERVING COUNTER Custom Model No. SCSL-258 Packed: ea CounterCraft custom serving counter
218	1 ea	SERVING COUNTER Custom Model No. SCSL-258 Packed: ea CounterCraft custom serving counter
219	1 ea	SERVING COUNTER Custom Model No. SCSL-258 Packed: ea CounterCraft custom serving counter
801	1 ea	SLIDING GRILLE Custom Model No. Air Vista Packed: ea Cookson Sliding Grilles
901	1 ea	LABOR Custom Model No. Custom Packed: ea Labor per specifications. - Remove existing equipment and deliver to College Station ISD, Remove existing Grille and patch/paint as

Item	Qty	Description
		necessary, set in place new equipment.
		All disconnections and reconnections for all utilities by others.
902	1 ea	PRINTS Kommerical Kitchens Model No. Custom Packed: ea Submittal Prints
903	1 ea	PERFORMANCE BOND <Optional> Kommerical Kitchens Model No. Custom Packed: ea If a performance bond is required please add \$5,100.
		Note: This is an option and not included in total price.
		Total \$299,974.00

Acceptance: _____ Date: _____

Printed Name: _____

Project Grand Total: \$299,974.00

Kirby RESTAURANT EQUIPMENT
& CHEMICAL SUPPLY CO.

809 South Eastman Road • Longview, Texas 75802 • 903-757-2723 • 1-800-877-5472

College Station I.S.D. - Texas A&M Consolidated H.S.

We would like to submit the following base bid price of **\$313,775.00** for food service equipment as specified in Food Service section 11400. If Performance and Security Bond is required please add **\$2,500.00** to total.


---Price Includes : Delivery and set-in place all equipment for final connection by other trades. All new equipment started and tested by Kirby. Rough-in drawing's for equipment furnished by Kirby. Equipment books parts and service manual furnished. All equipment carries one, (1) year parts and labor, plus additional four (4) compressor warranty.

---Not part of our scope : All final electrical and plumbing connections. Electrical conduit, floor depressions, roof & wall penetrations, roof jacks, concrete slab(s), ductwork or fire wrap above finished ceiling. Cement or finished floor for walk-in cooler / freezer. Conduit under-slab for refrigeration lines, drink lines, computers or other equipment requiring underground conduit. Any upper structure for supporting of hanging pot racks furnished by General Contractor. Cement curbs for serving counters to sit on.

---We have reviewed no addenda for this project.

Call me at 1-800-877-5472 or fax 903-757-9519 with any questions.
We are looking forward to completing this project with you.

Sincerely,
Lewis Beville
Senior Project Estimator



Certificate of Residency

The State of Texas has passed a law concerning non-resident contractors. This law can be found in Texas Government Code under Chapter 2252, Subchapter A. In part, this law reads as follows:

Section 2252:001

- (3) "Non-resident bidder" refers to a person who is not a resident.
- (4) "Resident bidder" refers to a person whose principal place of business in this state, including a contractor whose ultimate parent company or majority owner has its principal place of business in this state.

Section 2252.002

A governmental entity may not award a governmental contract to a nonresident bidder unless the nonresident underbids the lowest bid submitted by a responsible resident bidder by an amount that is not less than the amount by which a resident bidder would be required to underbid the nonresident bidder to obtain a comparable contract in the state in which the nonresident's principal place of business is located.

I, Lewis Beville, certify that Tombell Corporation dba Kirby Restaurant Supply is, under Section 2252.001 (3) and (4), a Resident Bidder:

Lewis Beville



**Texas
Metal
Equipment
Company**

· **Houston** ·
6707 Mayard Road
Houston, Texas 77041
(713) 486-8722
(713) 486-0166 fax

· **Dallas** ·
8704 Royal Lane
Irving, Texas 75063
(214) 446-7200
(214) 446-7209 fax

H3331ST

DATE: Tuesday, April 22, 2014

PROPOSAL

We are pleased to submit for your consideration this proposal for the Texas A&M Consolidated High School - Colle
Base Bid exactly per contract documents, specification section 11400 pages 1-7, and drawings pages F1-FS4.

Base Bid: \$ **309,498.00**

THIS BID PROPOSAL DOES NOT INCLUDE TAX.

THIS BID PROPOSAL DOES NOT INCLUDE BOND.

BOND (if required) \$3,100.00

This proposal recognizes no addenda.

This quote is valid for 30 days, with installation within 10 months of proposal date. After this time, quoted values may be subject to price change.

This proposal is based on the specification section listed above, pages as listed, drawings as listed, and addenda as listed. We will not be responsible for supply or verifications of details that appear in any other sections.

Exceptions Taken: · Any Mechanical, Electrical or Plumbing including water piping to condensers is to be **By Others**.
 · Any penetration of building or roof, or any core-drilling, is **By Others**.
 · Walk-In Assembly leveling or sand bed is **By Others**.

Special Notes Proposal is based on limited Foodservice Specification. No demolition or other scope of work is or Exceptions: included in this proposal.

Clarifications: · We require Purchase Orders in lieu of Subcontract for any work of \$50,000 or less.
 · We will not accept a subcontract which indicates more than (5%) retainage held from payments.
 · This proposal must be made an exhibit to our subcontract
 · We reserve the right to ammend standardized subcontracts

This proposal is based off of the work described in the Section 11400 specifications including General Conditions as well as directives in the Itemized Specifications. The purpose of the subcontractor is to furnish labor, materials, and equipment as detailed in Specifications and Plans making a complete kitchen installation up to a point of final connection by MEP trades.
 · Submittals and Close-Out Documents provided in Electronic Format

Custom fabricated equipment will not be put into fabrication until all finished wall surfaces associated with the fabricated equipment are complete and actual wall dimensions can be obtained. Custom items and equipment are not subject to "no-cost" cancellation once they have begun or completed production.

All Electrical and Plumbing components supplied by this subcontractor including but not limited to faucets, valves, drains, vacuum breakers, solenoids, switches, walk-in assembly lights, and pendant lights will be furnished loose to superintendant for Mechanical, Electrical or Plumbing Installer.

All work by this subcontractor will be installed by non-union labor. Our fabrication facilities are Open Shop.

Warranty is valid for a period of one (1) year from the time of start-up and usage of the equipment. Any extended warranty afforded by manufacturer will be transferable to Owner. Any extended warranty beyond this is cost additive.

We thank you for this opportunity and look forward to working with you on this project.

Sincerely,

Stephen Trawnik strawnik@txmetalequip.com
Contract Estimation / Purchasing